


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number L-13

**History of original corner establishment:**

Corner was originally established under G. L. O. contract number 503, by W. B. Barr, during August 8, 1884. Surveyor General's notes state: "Set basalt stone 12 X 10 X 8 ins. 8 ins. in ground for 1/4 sec. cor. marked 1/4 on W. Side. From which a pine 48 ins. diam., bear N65°E, 54 lks. dist. marked 1/4S BT. A pine 24 ins. diam. bears S51 1/2°W, 75 lks. dist. marked 1/4S BT.



**Description of corner evidence found:**

Found no trace of record stone or bearing trees. Corner falls between two roads and the area has been logged of all large pine trees.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At surveyed point set 2 1/2" X 30" aluminum pipe and cap marked:

Set pipe 24" in the ground and mound of stone around to cap. From which by magnetic declination of N20°E:

A 16" Fir bears N46°E, 22.4 ft. scribed 1/4 S15 BT. A 12"

Fir bears S14°W, 33.2 ft. scribed 1/4 S16 BT. Painted

blazes red and 6" red band around. Placed 54-3s, 54-4s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-4 on a steel fence post 5' west of the corner.

T7S R44E  
1/4  
S16 + S15  
OR PLS 1051  
1985

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Joseph M. Gaarsland  
Orville G. Allen

May 8, 1985.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Barry B. Barbour*  
OREGON  
OCT. 17, 1975  
BARRY B. BARBOUR  
1051

Office of..... County Surveyor's..... County of..... Baker  
Oregon  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 1985.

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

FILED 11-7-85  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-44-103