


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Index File Number N-9

**History of original corner establishment:**

Corner was originally established under G. L. O. contract number 503, by W. B. Barr, during August 12, 1884. Surveyor General's notes state: "Set basalt rock 18 X 12 X 6 ins., 10 ins. in ground for cor. to secs. 16, 17, 20 & 21, marked with 3 notches on the S. & 4 notches on the E. edges. From wchi a fir 8 ins. diam., bears N47°E, 22 lks. dist. marked T7S R44E S16 BT. A fir 24 ins. diam. bears S67°E, 75 lks. dist. marked T7S R44E S21 BT. A fir 5 ins. diam. bears S52°W, 49 lks. dist. marked T7S R44E S20 BT. A fir 5 ins. diam. bears N72°W, 44 lks. dist. marked T7S R44E S17 BT.




**Description of corner evidence found:**

Found no trace of record stone or bearing trees. Surveyed point falls on steep north slope. The area was logged several years ago and most of the timber in the area is second growth.

**Description of monument and accessories established to perpetuate the original location of this corner:**

At surveyed point set 2 1/2" X 30" aluminum pipe and cap marked:



Set pipe 20" in the ground and mound of stone around to cap. From which by magnetic declination of N20°E:  
 A 14" Fir bears N65°E, 26.9 ft. scribed T7S R44E S16 BT. A 20" Fir bears S88°E, 35.6 ft. scribed T7S R44E S21 BT. A 10" Fir bears S37°W, 19.0 ft. scribed T7S R44E S20 BT. A 7" Fir bears N10°W, 19.0 ft. scribed T7S R44E S17 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-4s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-4 on a steel fence post 5' south of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Van K. Barbour  
 Daniel J. McMillan

August 24, 1985,

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Barry B. Barbour*

OREGON  
 OCT. 17, 1975  
 BARRY B. BARBOUR  
 1051

Office of.....County Surveyor's..... County of..... Baker.....  
 State of..... Oregon..... I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 1985.  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)