


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number N-13

History of original corner establishment:

Corner was originally established under G. L. O. contract number 503, by W. B. Barr, during August 8, 1884. Surveyor General's notes state: "Set post 4 ft. long 4 ins. diam., 24 ins. in ground for cor. to secs. 15, 16, 21 & 22, marked....., from which a pine 3 ins. diam. bears N51°E, 52 lks. dist. marked T7S R44E S15 BT. A pine 12 ins. diam. bears S14°E, 175 lks. dist. marked T7S R44E S22 BT. A fir 24 ins. diam. bears S42°W, 60 lks. dist. marked T7S R44E S21 BT. A fir 30 ins. diam. bears N43°W, 20 lks. dist. marked T7S R44E S16 BT."

DIAGRAM




Description of corner evidence found:

Found no trace of record post or bearing trees. This area was searched by my crew during 1982. Corner falls about 25 ft. east of a 30" pine that was opened several years ago.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" aluminum pipe and cap marked:
Set pipe 24" in the ground and mound of stone around to cap.



From which by magnetic declination of N20°E:
A 14" Fir bears N77°E, 40.1 ft. scribed T7S R44E S15 BT. A 10" Fir bears S12°E, 37.6 ft. scribed T7S R44E S22 BT. A 12" Pine bears S18°W, 25.0 ft. scribed T7S R44E S21 BT. An 11" Pine bears N08°W, 40.7 ft. scribed T7S R44E S16 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-4s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-4 on a steel fence post 5' north of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Rick Lusk
Michael A. Dodds

April 30, 1985.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour
OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor's..... County of..... Baker.....

State of..... Oregon..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 1985.

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 11-7-85
BAKER COUNTY SURVEYOR
SURVEY NO. 7-44-107

☆ GPO—798-276