


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number W-9

History of original corner establishment:

Not Set.



Description of corner evidence found:

None Found.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" aluminum pipe and cap marked:  
 Set pipe 18" in the ground to bedrock. No rock in the area.

T7S R44E  
 NL/16  
 S32 + S33  
 OR PLS 1051  
 1984

From which by magnetic declination of N20°E:  
 A 6" Fir bears S55°E, 28.2 ft. scribed NL/16 S33 BT.  
 An 8" Fir bears N70°W, 9.5 ft. scribed NL/16 S32 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-2 and 54-9 on a steel fence post 5' east and 54-2 on a steel fence post 5' south of the corner.

I hereby certify that the above corner monument was established as herein described.

Witnesses: Michael E. Marks  
 Robert W. Wilson

October 16, 1984.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Barry B. Barbour*

OREGON  
 OCT. 17, 1975  
 BARRY B. BARBOUR  
 1051

Office of.....County Surveyor..... County of.....Baker.....  
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.85  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

FILED 11-7-85  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 7-44-150