


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number W-13

History of original corner establishment:

Not Set.



Description of corner evidence found:

None Found.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" aluminum pipe and cap marked:
 Set pipe 24" in the ground. No rock in the area.
 From which by magnetic declination of N20°E:
 A 6" Fir bears N03 1/2°E, 29.9 ft. scribed NL/16 S34 BT.
 An 8" Pine bears S56°W, 27.1 ft. scribed NL/16 S33BT.
 Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-9 on a steel fence post 5' north of the corner.

T7S R44E
 NL/16
 S33 + S34
 OR PLS 1051
 1984

I hereby certify that the above corner monument was established as herein described.

Witnesses: Michael E. Marks
 Robert W. Wilson

October 17, 1984.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Barry B. Barbour
 OREGON
 OCT. 17, 1975
 BARRY B. BARBOUR
 1051

Office of.....County Surveyor..... County of.....Baker.....
 State of.....Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 1985.
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 11-7-85
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-44-153