


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number X-9

History of original corner establishment:

Corner was originally established under G. L. O. contract number 503, by W. B. Barr, during August 11, 1884. Surveyor General's notes state: "Set post 4 ft. long, 4 ins. diam. 24 ins. in ground for 1/4 sec. cor. marked 1/4S on the W. side. From which a fir 14 ins. diam. bears N35°W, 38 lks. dist. marked 1/4S BT. A fir 5 ins. diam. bears N45°E, 13 lks. dist. marked 1/4S BT."



Description of corner evidence found:

Found no trace of record post or bearing trees. About 60 feet ~~was~~ west, a location tag and a post with red paint. This corner was about 40 chains south of the section corner and found by Rose in 1942. The 1/4 section corner a mile to the west was found to be about 40 chains south of the section corner. From this information, it was determined that this corner should be set 40.00 chains south of the original section corner to the north.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" aluminum pipe and cap marked: Set pipe 24" in the ground. No rock in the area. From which by magnetic declination of N20°E: A 9" Tamarack bears N80°E, 28.2 ft. scribed 1/4 S33 BT. A 12" Tamarack bears S85°W, 41.9 ft. scribed 1/4 S32 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-4s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-2 and 54-4 on a steel fence post 5' north and placed 54-2 on a steel fence post 5' south of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Michael E. Marks Robert W. Wilson

October 16, 1984.

REGISTERED PROFESSIONAL LAND SURVEYOR

Barry B. Barbour OREGON OCT. 17, 1975 BARRY B. BARBOUR 1051

Office of... County Surveyor... County of... Baker... State of... Oregon... I hereby certify that the within instrument was filed in this office for record on the... day of... 19.85

Form R6-7100-57 (9/71)

☆ U.S. GOVERNMENT PRINTING OFFICE • 1983-793-276

FILED 11-7-85 BAKER COUNTY SURVEYOR SURVEY NO. 7-44-160