

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number Y-16

History of original corner establishment:

Not Set.

**DIAGRAM**

T7S R44E  
SE + S34  
1/16 RM

Description of corner evidence found:

None Found.

Description of monument and accessories established to perpetuate the original location of this corner:

Surveyed point falls on rock outcrop. Marked point with nail. Set 2 1/2" X 30" aluminum pipe and cap, 5.00 ft. north of surveyed point. Marked cap: From the surveyed point, by magnetic declination of N20°E:

5 FT. NO.  
T7S R44E  
SE + S34  
1/16 RM  
OR PLS 1051  
1984

An 18" Pine bears S78°W, 47.8 ft. scribed SE 1/16 S34 BT.  
A 15" Fir bears S25°E, 19.0 ft. scribed SE 1/16 S34 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-9 on a steel fence post 5' west of the corner. Set pipe 18" in the ground and mound of stone around to cap.

I hereby certify that the above corner monument was established as herein described.

Witnesses: Michael E. Marks  
Robert W. Wilson

October 18, 1984.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Barry B. Barbour*

OREGON  
OCT. 17, 1975  
BARRY B. BARBOUR  
1051

Office of.....County Surveyor..... County of..... Baker  
State of..... Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 1985  
..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED 11-7-85  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-44-175