


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number Y-23

History of original corner establishment:

Not Set.



Description of corner evidence found:

None Found.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked:
Set pipe 26" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E:
A 12" Fir bears S20°W, 17.9 ft. scribed CS 1/16 S36 BT.
A 15" Fir bears N19°W, 37.0 ft. scribed CS 1/16 S36 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-2 and 54-9 on a steel fence post 5' north and placed 54-2 on a steel fence post 5' west of the corner.

T7S R44E
C
S1/16 + S36
C
OR PLS 1051
1983

I hereby certify that the above corner monument was established as herein described.

Witnesses: Larry D. Shirley
Troy A. Slobig

November 4, 1983.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor..... County of.....Baker.....

State of.....Oregon....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 1985.

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 11-7-85
BAKER COUNTY SURVEYOR
SURVEY NO. 7-44-177