


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Snow Fork Tract

History of original corner establishment:

Unknown.



Description of corner evidence found:

Found 3/4" iron pipe, projecting 6" above the ground. A 28" Fir bears S85°W, 46.2 ft. and is scribed "1".

Description of monument and accessories established to perpetuate the original location of this corner:

Surveyed point is center of 3/4" pipe. Dug hole around pipe and set 2 1/2" X 30" galvanized pipe and brass cap over 3/4" pipe. Brass cap is marked: Set pipe 24" in the ground and mound of stone around to cap.

T7S R44E
S14 SFT
#1
#1
OR PLS 1051
1982

From which by magnetic declination of N20°E: A 12" Fir bears S05°W, 38.7 ft. scribed S14 SFT #1 BT. Painted blazes red and 6" red band around. Placed 54-8s, 54-9s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-9 on a steel fence post 5' south of the corner.

I hereby certify that the above corner monument was established as herein described.

Witnesses: Larry D. Shirley
Michael L. Cain

November 15, 1982.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour
OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor..... County of.....Baker.....

State of.....Oregon....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 1985.

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

FILED 11-7-85
BAKER COUNTY SURVEYOR
SURVEY NO. 7-44-178