


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Snow Fork Tract

History of original corner establishment:

Unknown.



Description of corner evidence found:

Found 6' steel fence post projecting 36" above the ground.

Description of monument and accessories I established to perpetuate the original location of this corner:

Surveyed point is marked center of 6' steel fence post.  
 Removed fence post and set 2 1/2" X 30" galvanized pipe  
 and brass cap marked:  
 Set pipe 25" in the ground and mound of stone around to  
 cap.

T7S R44E  
 S14 SFT  
 #4  
 OR PLS 1051  
 1982

From which by magnetic declination of N20°E:  
 A 24" Fir bears N87°E, 29.5 ft. scribed S14 SFT #4 BT. A 10" Fir bears  
 N58 1/2°W, 40.3 ft. scribed S14 SFT #4 BT. Painted blazes red and 6"  
 red band around. Placed 54-8s, 54-9s and brass washers stamped PLS 1051  
 on the bearing trees. Placed 54-2 and 54-9 on a steel fence post 5' south  
 and place 54-2 on a steel fence post, N83°W, 5' from the corner.

I hereby certify that the above corner monument was established as herein described.

Witnesses: Larry D. Shirley  
Michael L. Cain

November 15, 1982.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Barry B. Barbour*

OREGON  
 OCT. 17, 1975  
 BARRY B. BARBOUR  
 1051

Office of.....County Surveyor..... County of.....Baker.....  
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.85  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

FILED 11-7-85  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 7-44-180