

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Snow Fork Tract

History of original corner establishment:

Unknown.

DIAGRAM

T7S R44E
S14 SFT
#3 T #3

Description of corner evidence found:

Found 6' steel fence post projecting 18" above the ground.

Description of monument and accessories established to perpetuate the original location of this corner:

Surveyed point is marked center of 6' steel fence post.
Removed fence post and set 2 1/2" X 30" galvanized pipe
and brass cap marked:
Set pipe 25" in the ground. No rock in the area.
From which by magnetic declination of N20°E;
A 12" Pine bears S77°E, 48.4 ft. scribed S14 SFT #3 BT.
A 20" Fir bears N43°W, 38.8 ft. scribed S14 SFT #3 BT. Painted blazes
red and 6" red band around. Placed 54-8s, 54-9s and brass washers stamped
PLS 1051 on the bearing trees. Placed 54-2 and 54-9 on a steel fence post
S83°E, 5 feet and 54-2 on a steel fence post N84°W, 5 feet from the corner.

T7S R44E
S14 SFT
#3 T #3

OR PLS 1051
1982

I hereby certify that the above corner monument was established as herein described.

Witnesses: Larry D. Shirley
Michael L. Cain

November 16, 1982.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor..... County of Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 1985
..... by
(COUNTY OFFICIAL) (DEPUTY)