

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Show Fork Tract

History of original corner establishment:

Unknown.

DIAGRAM

T7S R44E
S14 SFT



Description of corner evidence found:

Found 6' steel fence post projecting 18" above the ground.

Description of monument and accessories established to perpetuate the original location of this corner:

Surveyed point is marked center of 6' steel fence post. Removed fence post and set 2 1/2" X 30" galvanized pipe and brass cap marked:
Set pipe 25" in the ground. No rock in the area.
From which by magnetic declination of N20°E:
A 14" Fir bears S08°W, 40.9 ft. scribed S14 SFT #4 BT.
A 16" Tamarack bears N81°W, 59.6 ft. scribed S14 SFT #4 BT. Painted blazes red and 6" red band around. Placed 54-8s, 54-9s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-2 and 54-9 on a steel fence post, S83 1/2°E, 5' and placed 54-2 on a steel fence post, S06 1/2°W, 5' from the corner.

T7S R44E
S14 SFT



OR PLS 1051
1982

I hereby certify that the above corner monument was established as herein described.

Witnesses: Larry D. Shirley
Michael L. Cain

November 16, 1982.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barchour

OREGON
OCT. 17, 1975
BARRY B. BARCHOUR
1051

Office of.....County Surveyor..... County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 1985

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 11-7-85
BAKER COUNTY SURVEYOR
SURVEY NO. 7-44-183

☆ GPO—798-276