

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number V-13 (+0.50)

History of original corner establishment:

Not Set.

DIAGRAM

T7S R44E
S-S 1/64
S28 + S27

Description of corner evidence found:

None Found.

Corner falls in Eagle Creek. Moved corner on line at N2° 43' 20" W, 125.00 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" aluminum pipe and cap marked:
Set pipe 22" in the ground and mound of stone around to cap.
From which by magnetic declination of N20°E:
A 16" Pine bears S84°E, 45.3 ft. scribed WC S/S 1/64 S27
BT. A 16" Fir bears N63°W, 61.7 ft. scribed WC S/S 1/64 S28
BT. Painted blazes red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-2 and 54-9 on a steel fence post 5' north and placed 54-2 on a steel fence post 5' south of the corner.

WC 125.00 FT NO
T7S R44E
S/S 1/64
S28 + S27
OR PLS 1051
1985

I hereby certify that the above corner monument was established as herein described.

Witnesses: Daniel J. McMillan
John C. Austin

June 13, 1985.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour
OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor.....County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the.....day of....., 19.85

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 11-7-85
BAKER COUNTY SURVEYOR
SURVEY NO. 7-44-186

☆ GPO-798-276