


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number W-13.25

History of original corner establishment:

Not set.



Description of corner evidence found:

None Found.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" aluminum pipe and cap marked:
 Set pipe 24" in the ground and mound of stone around to cap.
 From which by magnetic declination of N20°E:
 A 12" Pine bears N63°W, 99.3 ft. scribed C/W/W/NW 1/256 S34
 BT. A 9" Pine bears N39°W, 93.6 ft. scribed C/W/W/NW 1/256
 BT.; Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and
 brass washers stamped PLS 1051 on the bearing trees. Placed 54-2 and 54-9
 on a steel fence post 5' east and placed 54-2 on a steel fence post 5'
 north of the corner.

T7S R44E
C/W/W/NW

1/256 + S34

OR PLS 1051

1985

I hereby certify that the above corner monument was established as herein described.

Witnesses: Orville G. Allen
 Joseph M. Gaarsland

May 20, 1985.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor.....County of.....Baker.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the.....day of....., 19..85
by.....
 (COUNTY OFFICIAL) (DEPUTY)