


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number X-13.50

History of original corner establishment:

Not Set:



Description of corner evidence found:

None Found.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" aluminum pipe and cap marked: T7S R44E
C/W/W
1/64 + S34
Set pipe 26" in the ground and mound of stone around to cap. OR PLS 1051
From which by magnetic declination of N20°E: 1985
A 10" Pine bears N88 1/2°E, 21.3 ft. scribed C/W/W 1/64 S34
BT. A 12" Fir bears S85 1/2°W, 30.5 ft. scribed C/W/W 1/64
S34 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and
brass washers stamped PLS 1051 on the bearing trees. Placed 54-2 and 54-9 on
a steel fence post 5' north and placed 54-2 on a steel fence post 5' south of
the corner.

I hereby certify that the above corner monument was established as herein described.

Witnesses: Daniel J. McMillan
John C. Austin

June 21, 1985.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor..... County of.....Baker.....

State of.....Oregon..... I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 1985.

..... by

(COUNTY OFFICIAL)

(DEPUTY)