


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Index File Number X-14 (-0.50)

**History of original corner establishment:**

Not Set.



**Description of corner evidence found:**

None Found.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At surveyed point set 2 1/2" X 30" aluminum pipe and cap marked:  
 Set pipe 14" in the ground and mound of stone around to cap. From which by magnetic declination of N20°E:  
 A 16" Pine bears N47 1/2°E, 61.4 ft. scribed C/N/SW 1/64 S34 BT. An 18" Pine bears S83°W, 59.7 ft. scribed C/N/SW 1/64 S34 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-2 and 54-9 on a steel fence post 5' north and placed 54-2 on a steel fence post 5' east of the corner.

T7S R44E  
 C/N/SW  
 1/64 + S34  
 OR PLS 1051  
 1985

I hereby certify that the above corner monument was established as herein described.

Witnesses: Daniel J. McMillan  
John C. Austin

June 19, 1985.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Barry B. Barbour*

OREGON  
 OCT. 17, 1973  
 BARRY B. BARBOUR  
 1051

Office of.....County Surveyor..... County of.....Baker.....  
Oregon

State of.....; I hereby certify that the within instrument was filed in this office for record on the..... day of....., 1985.

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 11-7-85  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 7-44-204