


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number X-14.75 (-0.50)

History of original corner establishment:

Not Set.



Description of corner evidence found:

None Found.

Corner falls in Eagle Creek. Set Witness Corner west on line at S89° 16' 56" W 100.00 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" aluminum pipe and cap marked: WC 100.00 FT WT
 Set pipe 26" in the ground and mound of stone around to cap. T7S R44E
 From which by magnetic declination of N20°E; C/E/NE/SW
 A 14" Fir bears S68°E, 22.7 ft. scribed WC C/E/NE/SW 1/256 OR PLS 1051
 S34 BT. A 20" Fir bears N86 1/2°W, 26.1 ft. scribed WC 1985
 C/E/NE/SW 1/256 S34 BT. Painted blazes red and 6" red band
 around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on the bearing
 trees. Placed 54-2 and 54-9 on a steel fence post 5' west and placed 54-2 on
 a steel fence post 5' east of the corner.

I hereby certify that the above corner monument was established as herein described.

Witnesses: Daniel J. McMillan
John C. Austin

June 19, 1985.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of..... County Surveyor..... County of..... Baker.....
 State of..... Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.85
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 11-7-85
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-44-205