

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number Y-15.25

History of original corner establishment:

Not set.

**DIAGRAM**

T7S R44E  
C-W-W-SE  
1/256 + S34

Description of corner evidence found:

None Found.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" aluminum pipe and cap marked:  
Set pipe 22" in the ground and mound of stone around to cap.  
From which by magnetic declination of N20°E:  
A 12" Pine bears S87°W, 22.8 ft. scribed C/W/W/SE 1/256 S34 BT. 1985  
A 10" Pine bears S15 1/2°W, 19.1 ft. scribed C/W/W/SE 1/256 S34 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-2 and 54-9 on a steel fence post 5' north and placed 54-2 on a steel fence post 5' west of the corner.

T7S R44E  
C/W/W/SE

1/256 + S34

OR PLS 1051

1985

I hereby certify that the above corner monument was established as herein described.

Witnesses: Orville G. Allen  
Joseph M. Gaarsland

May 22, 1985.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Barry B. Barbour*  
OREGON  
OCT. 17, 1975  
BARRY B. BARBOUR  
1051

Office of.....County Surveyor..... County of.....Baker.....  
State of.....Oregon..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 1985

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 11-7-85  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-44-207