

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**DIAGRAM**

**HISTORY OF ORIGINAL CORNER ESTABLISHMENT:**


**1/4 Corner of Sections 33/4**

**William B. Barr, June 24, 1884:**

Set a granite rock for 15 X 10 X 6 ins., 11 ins. in the ground for 1/4 Sec. Cor., marked 1/4 on N. side, from which:

A Tamarack, 6 ins. in diam., bears N 6 1/2°E, 225 lks. dist. marked 1/4 S.BT.

A Tamarack, 6 ins. in diam., bears N 3 1/2°W, 210 lks. dist. marked 1/4 S.BT.



**BLM, Lester E. Fischer, 1974**

Found:

A Western Larch, 16 ins. diam., N 6 1/2°E, 225 lks. dist., with healed double blaze.

A Western Larch, 17 ins. diam., N 3 1/2°W, 210 lks. dist., with illegible scribe marks on opened blaze.

Set:

An Iron post, 28 ins. long, 2 1/2 ins. diam., 22 ins. in the ground in a mound of stone, 2 1/2 ft. base to top, with brass cap mkd. as shown from which new bearing trees:

A Ponderosa Pine, 12 ins. diam., bears S 45°W., 127 lks. dist., mkd. 1/4 S4 BT

A Ponderosa Pine, 11 ins. diam., bears N 25 1/2°W, 78 lks. dist., mkd. 1/4 S33 BT.

**William L. Hanley, ORLS No. 1639, 1985**

Found:

Found 1974 BLM Brass Cap. (From Record of Survey Plat legend, East-Eagle Cadastral Survey)

**DESCRIPTION OF CORNER EVIDENCE FOUND:**

**Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008**

Found: 3 1/4 ins. BLM Brass Cap, on 2 ins. Iron Pipe., marked as shown.

A Fir snag bears N 6 1/2°E, 225 lks. dist. with exposed blaze

A Larch, 24 ins. in diam., bears N 3 1/2°W, 210 lks. dist. with exposed blaze

A Ponderosa Pine, 20 ins. diam., bears S 45°W., 127 lks. dist., with healed blaze

A Ponderosa Pine, 27 ins. diam., bears N 25 1/2°W, 78 lks. dist., with healed blaze.

**DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THE CORNER:**

New BT's:

A Fir, 18 ins. in diam., bears S 27°E, 20.6 ft. dist. marked 1/4 S.4 BT.

A Pine, 38 ins. in diam., bears N 45°W, 14.3 ft. dist. marked 1/4 S.33 BT.

Repainted existing BT's

**CORNER MONUMENT REFERENCES:**

I, Robert C. Lamburth certify that this corner was Properly re-established in 1974 and maintained on 6/29/08, as witnessed by K. Erich Shrack, LSIT

FILED OCTOBER 27, 2008  
BAKER COUNTY SURVEYOR  
SURVEY NO. 16-44-85 / 1-44-229  
CORNER PRES. NO. 129

