

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Original corner set by Barry B. Barbour, LS 1051, during survey filed with the Baker County Surveyor, file No. 7-44-78, said survey subsequently CANCELLED.

Record states:

At surveyed point set 2½" x 30" aluminum pipe and cap, set pipe 22" in the ground and mound of stone around cap.

From which:

A fir, 8 ins. diam., bears N. 40° E., 13.2 ft. dist., scribed S/N 1/64 S34 BT.

A fir, 10 ins. diam., bears S. 37° W., 39.8 ft. dist., scribed S/N 1/64 S33 BT.

Both bearing trees have brash washers stamped PLS 1051.

Corner reestablished by Rick E. Tawney, et al, under Group No. 1554, approved April 21, 1992.

Record states


Set a stainless steel post, 28 ins. long, 2½ ins. diam., 14 ins. in the ground, in a mound of stone, 2½ ft. base to top with brass cap.

From which bearing trees mkd. by Barbour

A fir, 8 ins. diam., bears N. 32° E., 16½ lks. dist., with scribe marks on partially healed blaze.

A fir, 10 ins. diam., bears S. 43¼° W., 63 lks. dist., with scribe marks on partially healed blaze.

Aluminum cap stamped by Barbour, PLS 1051, bears S. 85°48'00" W., 0.045 chs. dist.



**Description of corner evidence found:**

Found a 2½ ins. diam. steel pipe with a ¾ ins. diam. brass cap, mkd. as shown, firmly set, projecting 8 ins. above ground, in a rock collar,


From the recovered monument I find the bearing trees mkd. by Barbour

A Douglas fir snag, 8 ins. diam., bears N. 32° E., 10.9 ft. dist., with visible scribe on open blaze.

A fir, 13 ins. diam., bears S. 43¼° W., 41.4 ft. dist., with visible scribe on open blaze.

Found guard post 5 ft. South with Land Survey Monument (54-9) sign.

Found Barbour pipe, no cap, 3.0 ft., S. 85¼° W. of recovered monument.



**Description of monument and accessories I established to perpetuate original location of this corner:**

New bearing tree

A Douglas fir, 8 ins. diam., bears N. 89½° E., 3.9 ft. dist., mkd. S-N 1/64 S34 BT, with washer in side center.

CORS '02 geographic position:

Lat. 44°54'51.2" N  
Long. 117°19'17.9" W

All bearing trees are painted with red bands, and have Bearing Tree (54-3) and Land Survey Monument (54-9) signs attached. All new bearing trees have a metal washer stamped "LS 2648" nailed in the side center.

Posted National Forest Boundary N. 89°48'41" W. and S. 7°41'05" W. from corner with Property Boundary (54-2) signs, and a Land Survey Monument (54-9) sign on nearby post.

Witnesses: Kristina Powell, Matt Brockamp and Nick Tressler

Date: August 26, 2009

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Ron Walter*

OREGON  
JANUARY 18, 1994  
RON C. WALTER  
2648

Renewal Date: June 30, 2010

Office of ..... County Surveyor ..... County of ..... Baker .....  
State of ..... Oregon ..... , I hereby certify that the within instrument was filed in this office  
for record on the ..... day of ..... , 20 .....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

FILED Feb 24, 2010

Form R6-7100-57 (9/71)

BAKER COUNTY SURVEYOR  
SURVEY NO. 7-44-235