

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally set by Barry B. Barbour, LS 1051, during survey filed with the Baker County Surveyor, file no. 7-44-78 said survey subsequently CANCELLED.

Record states:

At surveyed point set 2½" x 30" aluminum pipe and cap, 22 ins. in the ground and mound of stone around to cap.

From which:

- A pine, 12 ins. diam., bears S. 87° W., 22.8 ft. dist., scribed C/W/W/SE 1/256 S34 BT.
- A pine 10 ins. diam., bears S. 15½° W., 19.1 ft. dist., scribed C/W/W/SE 1/256 S34 BT.

Both bearing trees have washers stamped PLS 1051.

Corner reestablished by Rick E. Tawney, et al, under Group No. 1554, approved April 21, 1992.


Record states:

Set a stainless steel post, 28 ins. long, 2½ ins. diam., 8 ins. in the ground, to solid rock, and in a mound of stone, 3 ft. base to top, with brass cap.

From which bearing trees mkd. by Barbour

- A pine, 12 ins. diam., bears S. 13° W., 30 lks. dist., with visible marks on partially healed blaze.
- A pine, 11 ins. diam., bears N. 84½° W., 40 lks. dist., with visible marks on partially healed blaze.

Aluminum cap stamped by Barbour, PLS 1051, bears N. 73°12'00" W., 0.055 chs. dist.




Description of corner evidence found:

Found a 2½ ins. diam. steel pipe with a ¾ ins. diam. brass cap, mkd. as shown, laying horizontal in stone mound. Found clear DEEP-1 magnet 12 ins. deep on solid rock.

From the location of magnet I find the bearing trees mkd. by Barbour

- A pine, 17 ins. diam., alive & healthy, bears S. 13° W., 19.8 ft. dist., with visible scribe on open blaze.
- A pine, 15 ins. diam., alive & healthy, bears N. 84½° W., 26.4 ft. dist., with visible scribe on open blaze.

Found Barbour cap N. 73¼° W., 3.6 ft. from recovered monument.



Description of monument and accessories I established to perpetuate original location of this corner:

Reset monument at location of magnet, which agrees with bearing-distance tree intersection, rebuild rock mound, with 4 ft. diam. base to top.

CORS '02 geographic position:

- Lat. 44°54'32.9" N
- Long. 117°18'41.8" W

All bearing trees are painted with red bands, and have Bearing Tree (54-3) and Land Survey Monument (54-9) signs attached.

Posted National Forest Boundary S. 89°10'19" W. and N. 6°25'37" E. from corner with Property Boundary (54-2) signs, and a Land Survey Monument (54-9) sign on nearby post.

Witnesses: Kristina Powell, Matt Brockamp and Nick Tressler

Date: August 18, 2009

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Ron Walter

OREGON
JANUARY 18, 1994
RON C. WALTER
2648

Renewal Date: June 30, 2010

Office of County Surveyor County of Baker

State of Oregon , I hereby certify that the within instrument was filed in this office
for record on the day of , 20

..... by

(COUNTY OFFICIAL) FILED Feb. 24, 2010 (DEPUTY)