

MINERAL SURVEY #126

Mineral survey #126 is located in sections 19 & 30, T.7S.R.44E. The original survey of MS 126 was performed in December 1882 which is before subdivisions of T.7S.R. 44E. were done, therefore the mineral survey tied to the section corner 19, 24, 25 & 30. The original call from corner #1 MS 126 to the section corner was $S82^{\circ}30'W$, 25.76 chains (1700.16') our tie to the section corner is shown of the accompanying plat.

The original corners were all 4"x4" wooden posts scribed "EMW No. "X" 126". At corners number 3 & 4 we found the rotted remains of squared posts with visible scribing. All corners have been updated through out the years with evidence of up to four rotted posts lying about the corners. All the posts are in mounds of rock.

As the evidence at these locations dates back many years and as no other evidence could be located in the vicinity to repudiate these corners I accept them as the best evidence of the original corners to mineral survey #126.

A closed traverse was run around MS #126 and the property line marked with steel fence posts and Forest Service property boundary signs. The corners of MS #126 were perpetuated with standard aluminum pipes and caps referenced to two bearing trees.

Instruments used were a Mac I-H Electronic Distance Measuring Device, Jena one-second theodolite, 4" K&E Staff Compass and 100' steel tape.

Bearings are based on solar observation.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet
C. E. S.
JULY 14, 1978
CARL E. SUNDET
16