


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. J-15

History of original corner establishment:

Corner established August 5, 1882, by W. B. Barr, under C.L.O. Contract No. 443. Surveyor General's notes state:

"Set Iron rock 14"x12"x5" 10" in the ground for 1/4 Sec. corner marked 1/4 on the north side from which: A Pine 9" in diam. bears N78°W, 47 lks dist. marked 1/4S BT. A Pine 9" in diam. bears S16°W, 40 lks dist. marked 1/4S BT."




Description of corner evidence found:

No trace of corner stone or bearing trees could be found.
 Corner falls on SE slope about 150' south of an east-west ridge.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" x 30" galvanized pipe with brass cap marked:
 Set pipe 26" in the ground and mound of stones to cap.



From which: A Pine 10" in diam. bears N23°E, 14.4 ft. scribed 1/4 S10 BT. A Pine 28" in diam. bears S12°E, 28.1 ft. scribed 1/4 S15 BT. Painted blazes red and 6" red band around. Placed 54-3s & 54-4s on BTs. Placed brass washer stamped PLS 1051 on foot blazes. Placed 54-4 on steel fence post 4' west of corner. Placed 54-5 on Pine 25' south of corner.

I hereby certify the above corner monument was reestablished as herein described.

Witnesses: David L. Landers
 Dan T. Rowland

August 4, 1978

**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

Barry B. Barbour

OREGON
 OCT. 17, 1975
BARRY B. BARBOUR
 1051

Office of County Surveyor County of Baker
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 25 day of August, 1978
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO 799-509

FILED Aug. 25, 1978

BAKER COUNTY SURVEYOR

SURVEY NO. 7-45-7