


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. L-13

History of original corner establishment:

Corner established August 5, 1882, by W. B. Barr, under G.L.O. Contract No. 443. Surveyor General's notes state:

"Set Basalt rock 18"x12"x5" 12" in the ground for 1/4 Sec. corner, marked 1/4 on west face from which: A Fir 9" in diam. bears N44°W, 16 lks dist. marked 1/4S BT. A Fir 4" in diam. bears N28°E, 13 lks dist. marked 1/4S BT."




Description of corner evidence found:

No trace of corner stone or BTs could be found. Area has not been logged but has been burned.

Corner falls on steep west slope about 150' east of small creek. G.L.O. calls and plat does not fit the area.

Description of monument and accessories | established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" x 30" galvanized pipe with brass cap marked:
Set pipe 25" in the ground and mound of stone around to cap.



From which: A Fir 3 1/4" in diam. bears N88°E, 41.7 ft. scribed 1/4 S15 BT. A Pine 16" in diam. bears S65°W, 74.5 ft. scribed 1/4 S16 BT. Painted blazes red and 6" red band around. Placed 54-3s & 54-4s on BTs. Placed brass washer stamped PLS 1051 on foot blazes. Placed 54-4 in steel fence post 5' north of corner. Placed 54-5 on small Pine 25' north of corner.

I hereby certify the above corner monument was reestablished as herein described.

Witnesses: David L. Landers
Jim McFarland

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of... County Surveyor... County of... Baker
State of... Oregon... I hereby certify that the within instrument was filed in this office

for record on the 25... day of... August... 19... 78

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

GPO 799-509

FILED Aug. 25, 1978

BAKER COUNTY SURVEYOR

SURVEY NO. 7-45-12