


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. N-15

History of original corner establishment:

Not set.



Description of corner evidence found:

None.

Corner falls on north edge of small ridge.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" x 30" galvanized pipe with brass cap marked:
Set pipe 25" in the ground and mound of stone to cap.

T7SR45E
S15
E — 1/16
S22
OR PLS 1051
1978

From which: A Pine 12" in diam. bears N35°E, 16.2 ft. scribed
E 1/16 S15 BT. A Fir 8" in diam. bears S05°E, 8.2 ft. scribed
E 1/16 S22 BT. Painted blazes red and 6" red band around. Placed
54-3s & 54-4s on BTs. Placed brass washer stamped PLS 1051 on foot
blazes. Placed 54-2 & 54-4 on steel fence post 5' north and 54-2 &
54-9 on steel fence post 5' east of corner. Placed 54-5 on small
Fir 7' south of corner.

I hereby certify the above corner monument was reestablished as herein described.

Witnesses: David L. Landers
Jim McFarland

July 28, 1978

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of..... County Surveyor..... County of..... Baker.....
State of..... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the 25 day of..... August....., 1978.
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO 799-509

FILED Aug. 25, 1978
BAKER COUNTY SURVEYOR
SURVEY NO. 7-45-13