


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. K-16

History of original corner establishment:

Not set.



Description of corner evidence found:

None.

Corner is on flat sandy area, east of track road. Corner is about 125' south of creek due to rip rap on bank. Placed 54-2 on steel fence post 85' north of corner at creek bank.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" x 30" galvanized pipe with brass cap marked:
Set pipe 24" in the ground and mound of stone around to cap.

T7SR45E
SO 178.85 FT

SWCNE	1/16 S15
OR	PLS 1051
1978	

From which: A 18" Fir bears S58°E, 21.8 ft. scribed SWCNE 1/16 S15 BT. The West Witness corner bears N10° 35' 33"W, 180.56 ft. Painted blazes red and 6" red band around. Placed 54-3 & 54-4 on BT. Placed brass washer stamped PLS 1051 on foot blaze. Placed 54-2, 54-4, & 54-9 in steel fence post 4' north of corner. Placed 54-5 on tree 20' east of corner.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

I hereby certify the above corner monument was reestablished as herein described.

Witnesses: David L. Landers
Dan T. Rowland

August 11, 1978

Office of.....County Surveyor..... County of..... Baker.....
State of.... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 25th day of..... August..... 1978

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO 799-509

FILED Aug. 25, 1978

BAKER COUNTY SURVEYOR

SURVEY NO. 7-45-17