

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

NO RECORD,

DIAGRAM

775 R45E
$E \frac{1}{16} \cdot \frac{529}{532}$
1979
RLS 934

Description of corner evidence found:

NONE

Description of monument and accessories I established to perpetuate the

original location of this corner: AT PROPORTIONED LOCATION I SET A 2" x 30" GALV. IRON PIPE W/ BRASS CAP STAMPED AS SHOWN ABOVE, FROM WHICH:

NEW BT, 12" PINE, SCRIBED "E 1/16 S32 BT" BEARS S20°W, 37.3 FT.

NEW BT, 11" FIR, SCRIBED "E 1/16 S29 BT, BEARS N53°W, 19.2 FT.

I SET THE 2" PIPE 28" IN GROUND AND SET STONES AROUND IT.

I SET A STEEL POST 3' E. OF COR AND A STEEL POST 3' S. OF COR., W/SIGNS 54-2 AND 54-9.

PAINTED A RED BAND AROUND BEARING TREES AND TAGGED THEM WITH SIGNS 54-3.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Victor M. McLind

OREGON
JULY 17, 1970
VICTOR M. McLIND
934

I HEREBY CERTIFY THE ABOVE CORNER MONUMENT WAS ESTABLISHED AS HEREIN DESCRIBED ON Nov. 14, 1979.

WITNESS: *George P. Buxtello*

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Boyle