

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: NONE

DIAGRAM
T75 R45E
S33
C-S-NE
1/64
1980
RLS 934

Description of corner evidence found: NONE

Description of monument and accessories I established to perpetuate the original location of this corner: AT CALCULATED POSITION I SET A 2" x 30" GALV. IRON PIPE W/ BRASS CAP STAMPED AS SHOWN ABOVE, FROM WHICH:
NEW BT, 8" PINE, SCRIBED "CS NE 1/4 S33 BT" BEARS S 25 1/2° E, 75.8 FT.
NEW BT, 12" PINE, SCRIBED "CS NE 1/4 S33 BT" BEARS N 54 1/2° E, 52.2 FT.
I SET THE 2" PIPE 26" IN GROUND AND SET STAKES AROUND IT.
I SET A STEEL FENCE POST 3' E. OF COR. W/ SIGN 54-2 & 54-9, AND A STEEL FENCE POST 3' N. OF COR. W/ SIGN 54-2.
I PAINTED A RED BAND AROUND BOTH BT'S AND TAGGED THEM W/ SIGN 54-3.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Victor M. McLind
OREGON
JULY 17, 1970
VICTOR M. McLIND
934

I HEREBY CERTIFY THE ABOVE CORNER MONUMENT WAS ESTABLISHED AS HEREIN DESCRIBED ON JUNE 20, 1980

WITNESS: *Don McFie*

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Aug. 11, 1980
BAKER COUNTY SURVEYOR
SURVEY NO. 7-45-54

☆ GPO-798-276