


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: NONE



Description of corner evidence found: NONE

Description of monument and accessories I established to perpetuate the

original location of this corner: AT CALCULATED POSITION I SET A 2" X 30" GALV. IRON

PIPE W/ BRASS CAP STAMPED AS SHOWN ABOVE, FROM WHICH:

NEW BT, 8" FIR, SERIATED "SN 1/64 S34 BT" BEARS S 61 1/2° E 110.5 FT.

NEW BT, 12" TAMPAK, SCRIBED "SN 1/64 S33 BT" BEARS N 10 1/2° W, 222.4 FT.

I SET THE 2" PIPE 28" IN GROUND AND SET STONES AROUND IT.

I SET A STEEL POST 3' S. OF COR. AND A STEEL POST 3' W. OF COR., W/ SIGNS 54-2 AND 54-9.

I PAINTED A RED BAND AROUND BOTH BT'S, AND TAGGED THEM W/ SIGNS 54-3

I HEREBY CERTIFY THE ABOVE CORNER MONUMENT WAS ESTABLISHED AS HEREIN DESCRIBED ON NOVEMBER 13, 1979.

WITNESS: George P. Burtell

REGISTERED PROFESSIONAL LAND SURVEYOR

Victor M. McLind

OREGON JULY 17, 1970 VICTOR M. McLIND 934

Office of..... County of..... State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19..... by..... (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Aug. 11, 1980 BAKER COUNTY SURVEYOR SURVEY NO. 7-45-55

☆ GPO-798-276

G. Burtell