


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N=23

History of original corner establishment:

Corner was established in 1882 by W. B. Barr, Deputy Surveyor under contract No. 443. Surveyor General's records state: Set post 4' long, 4" dia., 24" in the ground for 1/4 Sec. corner. marked 1/4 S on the North Side, from which:
A Fir 6" dia. bears N 18 E, 24 lks. dist. marked 1/4 S BT.
A Pine 6" dia. bears S 20 W, 27 lks. dist. marked 1/4 S BT.



Description of corner evidence found:

Found no trace of original corner due to ancient logging operation as well as recent logging. Also I found that the topog calls would not agree with one another.

Description of monument and accessories I established to perpetuate the original location of this corner:

I located this corner by single proportionate measurements and set a 2 1/2" brass cap on a 30" galv. iron pipe 4" above the surface of the ground. I then set two new bearing trees:

A Pine 9" dia. bears N 45 00 W, 5.0' horiz. dist. and scribed 1/4 S S133 BT.

A Doug. fir 6" dia. bears S 23 00 E, 22.0' horiz. dist. and scribed 1/4 S S24 BT.

I hereby certify the above corner monument was established as herein described during June 1981.

REGISTERED PROFESSIONAL LAND SURVEYOR

James H. Hambleton

OREGON JULY 10, 1954 JAMES H. HAMBLETON 645

Witnesses: *Mike Cain*
Mike Cain, Inst. Man

Mark Cain
Mark Cain, Chainman

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

COUNTY OFFICIAL

(DEPUTY)