

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-24

History of original corner establishment:

No previous history.

**DIAGRAM**

Cap Stamped  
T 7 S  
C-E-1/16  
S 24  
R 45 E  
1981  
ORLS 645

Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner:

At the 1/16 corner location I set a 2 1/2" brass cap on a 30" galv. iron pipe 22" above the surface of the ground in a large mound of stone 4' dia. and 2' high covering the monument, from which I set two bearing trees:

A Pine 10" dia. bears N 36 00 E, 41.25' horiz. dist. and scribed <sup>E</sup> 1/16S S24 BT.

A Pine 10" dia. bears N 81 00 E, 45.10' horiz. dist. and scribed <sup>E</sup> 1/16S S24 BT.

I hereby certify the above corner monument was established as herein described during June 1981.

Witnesses:

Mike Cain  
Mike Cain, Inst. Man

Mark Cain  
Mark Cain, Chairman

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*James H. Hambleton*

OREGON  
JULY 10, 1864  
JAMES H. HAMBLETON  
645

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED July 2, 1981  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-45-92

☆ GPO—798-276