


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number G-15-G16

History of original corner establishment:

Not Set.



Description of corner evidence found:

None Found.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked:  
Set pipe 25" in the ground and mound of stone around to cap.

T7S R44E  
C-W-E 1/64  
+  
S10  
OR PLS 1051  
1982

From which by magnetic declination of N20°E:  
A 7" Tamarack bears S86°E, 15.8 ft. scribed CWE 1/64 S10 BT.  
A 12" Fir bears N73°W, 18.6 ft. scribed CWE 1/64 S10 BT. Painted blazes red and 6" red band around. Placed 54-2s, 54-9s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-2 and 54-9 on a steel fence post 5' north and placed 54-2 on a steel fence post 5' south of the corner.

I hereby certify that the above corner monument was established as herein described.

Witnesses: Larry D. Shirley  
Terry J. Anderson

August 27, 1982.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Barry B. Barbour*

OREGON  
OCT. 17, 1975  
BARRY B. BARBOUR  
1051

Office of..... County Surveyor..... County of..... Baker  
State of..... Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 1985.  
..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

FILED 11-7-85  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-45-127