


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number G-17

History of original corner establishment:

Corner was originally established under G. L. O. contract number 443, by W. B. Barr, on August 2, 1882. Surveyor General's notes state: "Set Granite rock 20 X 14 X 10 ins. 15 inches in ground for 1/4 Sec. corner, marked 1/4 on West side, from which a Pine 9 in. diam. bears N35°W, 37 lks. dist. marked 1/4S BT. A Pine 28 ins. diam. bears N30°E, 37 lks. dist. marked 1/4S BT."



Description of corner evidence found:

Found no trace of record stone or bearing trees. Area has been logged and there are several skid roads in the area. This corner was searched for in 1979 and again this year.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked:
Set pipe 26" in the ground and mound of stone around to cap.
From which by magnetic declination of N20°E:
An 18" Fir bears S17°E, 16.7 ft. scribed 1/4 S11 BT. A 9" Pine bears S47°W, 27.8 ft. scribed 1/4 S10 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-4s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-4 on a steel fence post 5' south of the corner.

T7S R45E
1/4
S10 + S11
OR PLS 1051
1982

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Larry D. Shirley
Terry J. Anderson

August 30, 1982.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor..... County of.....Baker.....
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 1985.

..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED 11-7-85
BAKER COUNTY SURVEYOR
SURVEY NO. 7-45-128