


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Not previously established.



Description of corner evidence found:

Not previously established.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 30" long aluminum pipe with a 3 1/2" aluminum cap, marked as shown above, 7" above ground. Steel post with signs 54-9 & 54-2 next to cap.

Scribed:

10" fir S.04°W. 42.0' "C 1/4 S34 BT"

11" fir N.73°W. 34.2' "C 1/4 S34 BT"

Attached signs 54-3 & 54-9 and nailed aluminum washers stamped "RLS 1928" by "BT" scribe on both trees. Painted blazes red and a 6" red band around each tree.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
1-20-86
Duane Fehring
OREGON
JULY 13, 1984
DUANE FEHRINGER
2118

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

FILED May 9, 1986
BAKER COUNTY SURVEYOR
SURVEY NO. 7-45-142