

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by W. B. Barr under Contract No. 443, dated May 29, 1882.

Surveyor's General record states:

Set post 4 ft. long, 4 in. diam., 24 inches in ground for corner to Sec. 15, 16, 21, 22 marked T 7 S 15 on NE face, R 46 E S 22 on SE face, S 21 on the SW face and S 16 on the NW face with 3 notches on the South and East edges from which


- A fir, 14 ins. diam. bears N 71° E 9 lks., dist. marked T 7 S R 46 E S 15 BT
- A fir, 3 ins. diam. bears N 3° W 47 lks., dist. marked T 7 S R 46 E S 16 BT
- A fir, 16 ins. diam. bears S 35° W 28 lks., dist. marked T 7 S R 46 E S 21 BT
- A fir, 15 ins. diam. bears S 33° E 17 lks., dist. marked T 7 S R 46 E S 22 BT

Description of corner evidence found:

- A fir with blaze bears S 35° E. 28 lks. dist.
- A fir (blown down and rotting) bears N 71° E. 9 lks. dist.

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2 inch aluminum cap on a 1 inch iron pipe, 28 inches long, 22 inches in the ground, marked thus:



Office of Baker County Surveyor, County of Baker
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the _____ day of _____
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

FILED 7-12-74
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-46-3

