

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by W. B. Barr under Contract No. 443, dated May 29, 1882.

Surveyor's General record states:

Set basalt rock 14 ins. x 10 ins. x 9 ins., 10 inches in the ground for corner to Sec. 14, 15, 22, 23 marked with 2 notches on the East and 3 notches on the South edges, from which


- A pine 6 ins. diam. bears N. 63° E. 96 lks., dist. marked T 7 S R 46 E S 14 BT
- A pine 15 ins. diam. bears N. 39° W. 90 lks., dist. marked T 7 S R 46 E S 15 BT
- A pine 30 ins. diam. bears S. 67° W. 77 lks., dist. marked T 7 S R 46 E S 22 BT
- A pine 40 ins. diam. bears S. 15° E. 62 lks., dist. marked T 7 S R 46 E S 23 BT

Description of corner evidence found:

Found unmarked stone of record dimensions, 4-inch square wood post with Forest Service cruiser tag attached, and one bearing tree in poor condition.

Description of monument and accessories established to perpetuate the original location of this corner

Set 2 inch aluminum cap on 1 inch iron pipe, 28 inches long, 22 inches in the ground, marked thus:



New bearing trees:

- A pine, 18 ins. in diam. bears N. 71° 30' E. 15.7 ft.
- A pine, 11 ins. in diam. bears S. 46° E. 24.4 ft.
- A pine, 9 ins. in diam. bears S. 41° 30' W. 37.5 ft.
- A pine, 10 ins. in diam. bears N. 52° 30' W. 22.5 ft.

Office of.....County Surveyor..... County of.....Baker.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the day of
 by
 (COUNTY OFFICIAL) (DEPUTY)

FILED 7-12-74
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-46-7

