

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by W. B. Barr under Contract No. 443, dated May 29, 1882.

Surveyor's General record states:

Set post 4 ft. long, 4 in. diam., 2 ft. in ground for 1/4 Sec. corner marked 1/4 on the North side, from which

A pine, 20 ins. diam. bears N. 42° E. 54 lks., dist. marked 1/4 S BT
A pine, 10 ins. diam. bears S. 72° W. 65 lks., dist. marked 1/4 S BT



Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner

Set 2 inch aluminum cap on a 1 inch iron pipe, 28 inches long, 22 inches in ground, marked thus:

T 7 S R 46 E
 $\frac{1}{4}$ $\frac{S 16}{S 21}$
 CS 1974

New bearing trees:

A pine, 10 ins. diam. bears N. 53° 30' W. 8.3 ft.
A pine, 12 ins. diam. bears S 2° E. 17.2 ft.

Office of County Surveyor County of Baker
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the _____ day of _____
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

FILED 7-12-74
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-46-10

