


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by W.B. Barr under GLO Contract No. 443 dated May 29, 1882.

Surveyor General's records state:

Set basalt rock 14x8x6 ins 10 ins in ground for 1/4 Sec corner marked 1/4 on the North side from which:



A pine 24 ins diam bears S 25° W, 108 lks dist mkd 1/4 S BT  
A pine 18 ins diam bears N 20° W, 275 lks dist mkd 1/4 S BT

Description of corner evidence found:

Found a 32 inch stump sawed at 12 ins with BT scribes visible.

Could not find section 14 BT or the corner stone.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½ inch brass cap on a 2 inch iron pipe 31 ins long 26 ins in the ground with a 6 ft steel fence post 4 ft West with a sign 54-4 attached.

Brass cap marked thus: T 7 S R 46 E

$\frac{1}{4}$        $\frac{S 14}{S 23}$

1979  
ORLS 1639

New bearing trees:

A fir 10 ins diam bears N 76° W., 43.1 ft dist mkd 1/4 S 14 BT  
A pine 10 ins diam bears S 30° W., 42.1 ft dist mkd 1/4 S 23 BT

The original BT stump has a sign 54-3 attached and each new BT has a sign 54-3 attached 6 ins below a red band of paint and has a brass washer marked LS 1639 nailed flush with BT blaze.

I hereby certify the above corner monument was properly re-established on July 2, 1979 witnessed by Tracy Labaree and Jim DeMastus.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William L Hanley*

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-51 (9/71)

FILED July 16, 1979  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-46-17