


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.



Description of corner evidence found:

At calculated corner location found a wooden stake in small rock mound - rocks painted yellow.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2½ inch brass cap on a 2 inch iron pipe 31 ins long 27 ins in the ground to solid rock with a surrounding rock mound and a 6 ft steel fence post alongside with 1 sign 54-9 and 2 signs 54-2 attached.

Brass cap marked thus: T 7 S R 46 E

W $\frac{1}{16}$ S $\frac{15}{22}$

1979

ORLS 1639

New bearing trees:

A fir 08 ins diam bears N. 26° E., 33.6 ft dist mkd W 1/16 S 15 BT
A pine 12 ins diam bears S. 74° E., 50.4 ft dist mkd W 1/16 S 22 BT

Each BT has a sign 54-3 attached 6 ins below a red band of paint and has a brass washer marked LS 1639 nailed flush with BT blaze.

I hereby certify that the above monument was properly established as herein described on July 18, 1979 witnessed by Tracy Labaree and Jim DeMastus.

REGISTERED PROFESSIONAL LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-51 (9/71)

FILED July 19, 1979
BAKER COUNTY SURVEYOR
SURVEY NO. 7-46-19