

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by W.B. Barr under GLO Contract No. 443 dated May 29, 1882.

Surveyor General's records state:

Set basalt rock 10 X 10 X 8 ins 7 ins in ground for corner to Sec 13, 14, 23, 24 marked with 3 notches on the South and 1 notch on the East edges from which:

- A pine 32 ins diam bears N 73° E 65 lks dist mkd T 7 S R 46 E S 13 BT
- A pine 14 ins diam bears N 06° W 82 lks dist mkd T 7 S R 46 E S 14 BT
- A pine 48 ins diam bears S 10° W 95 lks dist mkd T 7 S R 46 E S 23 BT
- A pine 36 ins diam bears S 83° E 107 lks dist mkd T 7 S R 46 E S 24 BT



Description of corner evidence found:

A stone 10x10x8 ins in place with 1 notch on East edge.

- A sawed pine stump for Section 13 BT with no visible scribes
- A sawed pine stump for Section 14 BT with no visible scribes
- A burned snag stump for Section 23 BT with no visible scribes
- The rotten remains of a large tree for Section 24 BT

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2½ inch brass cap on a 2 inch iron pipe 31 ins long 27 ins in the ground with a 6 ft steel fence post alongside with a sign 54-4 attached.

Brass cap marked thus:

T 7 S	R 46 E
S 14	S 13
S 23	S 24
1979	
ORLS 1639	

New bearing trees:

- A fir 08 ins diam bears N 44° E, 48.0 ft dist T 7 S R 46 E S 13 BT
- A pine 06 ins diam bears S 53° E, 43.8 ft dist T 7 S R 46 E S 24 BT
- A pine 12 ins diam bears S 08° W, 60.6 ft dist T 7 S R 46 E S 23 BT
- A pine 08 ins diam bears N 35° W, 40.7 ft dist T 7 S R 46 E S 14 BT

Each original BT has a sign 54-3 attached and each new BT has a sign 54-3 attached below a band of red paint and has a brass washer nailed flush with BT blaze.

I hereby certify that the above monument was properly re-established as herein described on July 31, 1979 witnessed by Jim DeMastus and Tracy Labaree.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William L. Hanley*

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Aug. 1, 1979  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-46-28

☆ GPU 799-509