

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by W.B. Barr under GLO Contract No. 443 dated May 29, 1882.

Surveyor General's records state:

Set basalt rock 16 X 14 X 12 ins 11 inches in the ground for 1/4 Sec corner marked 1/4 on West side, from which:

A pine 10 ins diam bears N 84° W 66 lks dist mkd 1/4 S BT
A pine 32 ins diam bears N 20° E 24 lks dist mkd 1/4 S BT



Description of corner evidence found:

A rotten pine windblow with full scribes for original Sec 15 BT

Found a 2½ inch aluminum cap marked thus: T 7 S R 46 E
S 15 | S 14
CS 1974

A dead pine 12 ins diam bears S 21° 30' E, 30.5 ft dist mkd W 1/4 S 14 BT
A pine 11 ins diam bears N 36° 30' W, 23.8 ft dist mkd E 1/4 S 15 BT

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 6 ft steel fence post 5 ft West with a sign 54-4 attached and improved rock mound.

A pine 8 ins diam bears S 08° E, 53.3 ft dist mkd X BT with a sign 54-3 attached below a band of red paint and has a brass washer marked LS 1639 nailed flush with BT blaze.

Placed a sign 54-3 on original Section 15 BT and painted blazes red. Painted the other BT with a band of red paint.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

I hereby certify that the above monument was properly re-established as herein described on August 3, 1979 witnessed by Tracy Labaree and Jim DeMastus.

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Aug. 9, 1979
BAKER COUNTY SURVEYOR
SURVEY NO. 7-46-30