

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by W.B. Barr under GLO Contract No. 443 dated May 29, 1882.

Surveyor General's records state:

Set volcanic rock 13 X 8 X 6 ins 9 ins in ground for 1/4 Sec corner marked 1/4 on the North side, from which:

A pine 09 ins diam bears N 28° W 21 lks dist mkd 1/4 S BT
A pine 10 ins diam bears S 12° W 53 lks dist mkd 1/4 S BT



Description of corner evidence found:

A pine 30 ins diam with BT scribes on previously opened blaze for original Sec 15 BT

Found a 2½ inch aluminum cap on a 1 inch iron pipe marked T 7 S R 46 E
 $\frac{1}{4}$ $\frac{S 10}{S 15}$
CS 1974

A fir 18 ins diam bears S 17°30' E, 24.5 ft dist mkd N 1/4 S 15 BT
A fir 14 ins diam bears N 16°30' E, 22.2 ft dist mkd S 1/4 S 10 BT

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 6 ft steel fence post alongside aluminum cap monument with a sign 54-4 and 2 signs 54-2 attached. Improved rock mound surrounding corner monument and painted red band of paint on each BT and placed a sign 54-3 on original Sec 15 BT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

I hereby certify that the above monument was properly re-established as herein described on August 3, 1979 witnessed by Tracy Labaree and Jim DeMastus.

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Aug. 9, 1979
BAKER COUNTY SURVEYOR
SURVEY NO. 7-46-31