


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.



Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½ inch brass cap on a 2 inch iron pipe 31 ins long 28 ins in the ground with a surrounding rock mound and a 6 ft steel fence post 5 ft North with a sign 54-9 attached.

Brass cap marked thus: T 7 S R 46 E  
C ¼ S 22  
1979  
ORLS 1639

New bearing trees:

A pine 06 ins diam bears S 07° E, 41.2 ft dist mkd C 1/4 S 22 BT  
A pine 12 ins diam bears N 68° W, 15.7 ft dist mkd C 1/4 S 22 BT

Each BT has a sign 54-3 attached below a band of red paint and has a brass washer marked LS 1639 nailed flush with BT blaze.

I hereby certify that the above monument was properly established this survey as herein described on August 3, 1979 witnessed by Tracy Labaree and Jim DeMastus.



Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-5/ (9/71)

FILED Aug 9, 1979  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-46-32