


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.




Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½ inch brass on a 2 inch iron pipe 31 ins long 27 ins in the ground with a surrounding rock mound and a 6 foot steel fence post alongside with a sign 54-2 and 54-9 attached.

Brass cap marked thus: T 7 S R 46 E



New bearing trees:

A pine 18 ins diam bears N 46° W., 192.0 ft dist marked S 1/16 S 16 BT
An alder 6 ins diam bears N 71° E., 42.5 ft dist marked S 1/16 S 15 BT

Each bearing tree has a sign 54-3 attached below a band of red paint and has a brass washer marked LS 1639 nailed flush with BT blaze.

I hereby certify that the above corner monument was properly established by me on August 13, 1979 and witnessed by Tracy Labaree.

REGISTERED PROFESSIONAL LAND SURVEYOR

William L. Hanley

OREGON JULY 14, 1978 WILLIAM L. HANLEY 1639
--

Office of County Surveyor..... County of..... Baker.....
State of... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-5/ (9/71)

FILED Aug. 16, 1979
BAKER COUNTY SURVEYOR
SURVEY NO. 7-46-38