

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.

DIAGRAM

T 7 S R 46 E

SW $\frac{1}{16}$ S 24

Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½ in. brass cap on a 2 in. iron pipe 31 ins. long 27 ins. in the ground with a surrounding rock mound and a 6 ft. steel fence post alongside with a sign 54-9 and 2 signs 54-2 attached.

Brass cap marked thus: T 7 S R 46 E

SW $\frac{1}{16}$ S 24

1979
ORLS 1639

New bearing trees:

A pine, 8 inch diam. bears N 14° E., 42.7 ft. dist. marked SW 1/16 S 24 BT
A pine, 6 inch diam. bears S 47° E., 31.8 ft. dist. marked SW 1/16 S 24 BT

Each new bearing tree has a sign 54-3 attached below a band of red paint and has a brass washer marked LS 1639 nailed flush with BT blaze.

I hereby certify the above corner monument was properly established by me on Sept. 13, 1979 and witnessed by Tom Fisk and Jeff Townsend.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-5/ (9/71)

FILED Sept. 20, 1979
BAKER COUNTY SURVEYOR
SURVEY NO. 7-46-45