


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.



Description of corner evidence found:

A fence line bears North, 25.0 ft. dist. from which the fence runs east and west.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½ in. brass cap on a 2 in. iron pipe 31 ins. long 29 ins. in the ground with a surrounding rock mound and a 6 foot steel fence post alongside with a sign 54-9 and 2 signs 54-2 attached.

Brass cap marked thus:

T 7 S R 46 E
W $\frac{1}{16}$ S $\frac{24}{25}$

1979

ORLS 1639

New bearing trees:

A pine 6 ins. diam. bears N 13° E, 9.4 ft. dist. marked W 1/16 S 24 BT
A pine 13 ins. diam. bears S 03° E, 6.8 ft. dist. marked W 1/16 S 25 BT

Each new bearing tree has a sign 54-3 attached below a band of red paint and has a brass washer marked LS 1639 nailed flush with BT blaze.

I hereby certify the above corner monument was properly established by me on Sept. 13, 1979 and witnessed by Tom Fisk and Jeff Townsend.

REGISTERED PROFESSIONAL LAND SURVEYOR

William L. Hanley

OREGON JULY 14, 1978 WILLIAM L. HANLEY 1639
--

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Sept. 25, 1979
BAKER COUNTY SURVEYOR
SURVEY NO. 7-46-59