


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.



Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½ in. brass cap on a 2 in. iron pipe 31 ins. long 27 ins. in the ground with a surrounding rock mound and a 6 foot steel fence post alongside with a sign 54-9 and 2 signs 54-2 attached.

Brass cap marked thus:

T 7 S R 46 E

W  $\frac{1}{16}$  S  $\frac{23}{26}$

1979

ORLS 1639

New bearing trees:

A pine 8 ins. diam. bears S 35° E, 45.0 ft. dist. marked W 1/16 S 26 BT  
A pine 6 ins. diam. bears N 78° E, 104.4 ft. dist. marked W 1/16 S 23 BT

Each new bearing tree has a sign 54-3 attached below a band of red paint and has a brass washer marked LS 1639 nailed flush with BT blaze.

I hereby certify the above corner monument was properly established on Sept. 10, 1979 by me and witnessed by Jim DeMastus and Jeff Townsend.

REGISTERED PROFESSIONAL LAND SURVEYOR
---

*William L Hanley*

OREGON JULY 14, 1978 WILLIAM L. HANLEY 1639
--

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-51 (9/71)

FILED Sept. 25, 1979

BAKER COUNTY SURVEYOR

SURVEY NO. 7-46-62