


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by W.B. Barr under GLO Contract No. 443 dated May 29, 1882.

Surveyor General's records state:

Set basalt rock 15 X 10 X 8 ins 10 ins in ground for 1/4 Sec corner marked 1/4 on the West side; dug pits 18 X 18 X 12 ins 5 1/2 ft dist North and South of stone and raised mound of earth 1 1/2 ft high 3 1/2 ft base alongside; pits impracticable.




Description of corner evidence found:

A basalt stone 15 x 10 x 8 ins. 10 ins. in the ground marked 1/4.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2 in. brass cap on a 2 in. iron pipe 31 ins. long 26 ins. in the ground with a surrounding rock mound and a 6 foot steel fence post alongside with a sign 54-4 and 2 signs 54-2 attached. Buried original stone alongside.

Brass cap marked thus: T 7 S R 46 E



ORLS 1639

There being no trees available within limits I raised a mound of stone, the nearest point of which bears West, 3.0 ft. dist.

I hereby certify that the above corner monument was properly remonumented by me on August 8, 1979 and witnessed by Jim DeMastus.

REGISTERED PROFESSIONAL LAND SURVEYOR
--

William L Hanley

OREGON JULY 14, 1978 WILLIAM L. HANLEY 1639

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED Oct. 23, 1979
BAKER COUNTY SURVEYOR
SURVEY NO. 7-46-68