

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

0-3

History of original corner establishment:

No previous history.

DIAGRAM

Cap Stamped
T 7 S
C-N-1/16
S 19
R 46 E
1981
ORLS 645

Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner:

At the 1/16 corner location I set a 2 1/2" brass cap on a 30" galv. iron pipe at surface of ground, from which I set two bearing trees:

A Doug. fir 13" dia. bears S 20 00 E, 21.72' horiz. dist. and scribed N 1/16 S 19 BT.

A Doug. fir 5" dia. bears S 87 30 W, 24.79' horiz. dist. and scribed N 1/16 S 19 BT.

I hereby certify the above corner monument was established as herein described during June 1981.

Witnesses:

Mike Cain

Mike Cain, Inst. Man

Mark L Cain

Mark Cain, Chainman

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James M. Hambleton

OREGON
JULY 13, 1954
JAMES M. HAMBLETON
645

Office of..... County of.....

State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

FILED July 2, 1981

BAKER COUNTY SURVEYOR

SURVEY NO. 7-46-89