

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-5

History of original corner establishment:

Corner was established in 1882 by W. B. Barr, Deputy Surveyor under contract No. 443. Surveyor General's records state: Set ironstone 13" x 8" x 6", 9" in ground for $\frac{1}{4}$ sec. corner marked $\frac{1}{4}$ on the West-side, from which:

A Pine 5" dia. bears N 41 E, 40 lks. dist. marked $\frac{1}{4}$ S BT.
A Pine 3" dia. bears S 42 W, 47 lks. dist. marked $\frac{1}{4}$ S BT.

DIAGRAM

Cap Stamped *60*

T 7 S R *46* E

$\frac{1}{4}$

S 19 | S 20

CS

1979

Description of corner evidence found:

At the assumed $\frac{1}{4}$ corner location I found no trace of the original corner as described in the GLO notes, however, I found a brass cap set by the County Surveyor in 1979 and being stamped as shown above.

Description of monument and accessories I established to perpetuate the original location of this corner:

From the above mentioned brass cap I set two bearing trees:

A Pine 12" dia. bears N 52 15 W, 27.25' horiz. dist. and scribed $\frac{1}{4}$ S S119 BT.

A Pine 13" dia. bears N 71 E, 25.0' horiz. dist. and scribed $\frac{1}{4}$ S S 20 BT.

I hereby certify the above corner monument was re-established as herein described during June 1981

Witnesses:

Mike Cain
Mike Cain, Inst. Man

Mark R. Cain
Mark Cain, Chainman

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton
OREGON
JULY 10, 1954
JAMES H. HAMBLETON
645